

Slice Test & Trigger Completion

Installation in Underground Counting Room

- Expect access by March '05
- Sufficient time for installation and some testing but not for completing commissioning with detectors

Slice Test (on surface)

- With both HCAL and EMU
- Verify trigger functions and interfaces by testing with detectors on surface at CERN.
- Suggest as substitute for commissioning completion step.
- Will check as much on surface before gaining access to underground facilities.

Planned for October '04 - March '05


Underground

Counting Room



Ingredients for Slice Test (whole system is one crate)

Single Track-Finder Crate Design with 1.6 Gbit/s optical links



- Reduces processing time from 525 ns (old design) to 175 ns
 - Total Latency ~ 20 Bx (from input of SR/SP card to output of MS card)
- Crate Power Consumption ~ 500 W 15 Optical connections per SR/SP card

US CMS FNAL Director's Review, May 1, 2002: Trigger Slice Test



CSC Trigger Slice Test

Requirements for 3-station 20 degree slice test of 12 CSCs (w/2 ME1/1):

- Need: 3 MPC, 1 SP/SR, 1 CCB module, 1 backplane
- Integrate w/3 partially populated peripheral crates + 1 DDU

Schedule:

- Apr-02 Prototype 2 designs done
- Nov-02 Prototype 2 construction done
- Apr-03 Prototype 2 testing done
- Sep-03 Final designs done
- CSC Sorter module: only 1, design by Jan-04
 - Not needed for Slice Test I: use trigger output from CCB
- Oct-04 Production done
- Mar-05 Installation begins in USC55

Slice Test Phase I

- Oct-03 to Oct-04
- Use Prototype 2 modules

Slice Test Phase II:

- Oct-04 to Mar-05
- Use Production Modules (& Proto. Sorter)



Slice Test DAQ (10-100 Hz)

